BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT30277

APPROVED SCHEDULE - B

EE/TP/BBMP/E-PMT/27/2017-18, Date: 07.03.2018

Improvements to roads and drains in Jakkur colony, in ward no. 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M. Prakash	
				In Figures	In Words
1	74.16	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	195.0	Rupees One Hundred Ninety Five Only
2	18.54	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5100.0	Rupees Five Thousand One Hundred Only
3	139.98	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4400.0	Rupees Four Thousand Four Hundred Only
4	391.4	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	100.0	Rupees One Hundred Only
5	37.08	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5700.0	Rupees Five Thousand Seven Hundred Only
6	247.2	Providing precast slab of 200mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	4980.0	Rupees Four Thousand Nine Hundred Eighty Only

M. Prakash

Signature of the Contractor

26/03

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/03